

**BOQ**

**Name of the Work : External colour and other related work for the Regional Blood Bank at DPTC building in the premises of IRCS-OSB , Bhubaneswar for the FY - 2022-23**

SI No	Items description	Unit	Quantity	Rate	Amount
1	Removing old lime or cement plaster from walls including raking out joints 12 mm deep & removing the debris with in 50. m Lead. Including the cost of all the materials , labour , Scaffolding , Sundries , T&P etc as required for the work and completed in all the respect .	sqm	19.52	39.341	767.94
2	12 mm thickinside plaster Cement Plaster(1:6) for brick work including cost of all materials , Labour, Scaffolding , Sundries , T&P etc as required for the work and completed in all the respect.( qnty as per actual).	sqm	19.52	136.05	2655.65
3	Scrapping old painting with scrapper in all floor at all height , sand papering , washing with soap water including sacffolding including cost of all all labour , sundries and T&P etc required for the work completed in all the respect	sqm	1378.25	4.67	6436.43
4	Painting 1 coat with approved primer to wall including cost of all the material , Labour , T&P , Scaffolding , sundries etc as required for the work completed in all the respect. ( qnty as per actual).	Sqm	19.52	60.386	1178.73
	Vide item No-2				
5	Painting 2 coats of weather coats with approved by Authority colour to wall including the cost of all the materials , labour , T&P , Scaffolding , sundries etc required for the work completed.( qnty as per actual).	Sqm	1378.25	74.303	102407.67
	Vide item No-3				
6	Paints two coats with any approved enamel paint to new iron/wood work over a coat of primer including cost , lead etc of all materials for new works & T&P , Scaffolding , sundries etc required for the work completed. .( qnty as per actual).	Sqm	52.76	137.59	7259.27
7	Cement Concrete of proof (1:2:4) using 12 mm size BHG mental including all material , labour cost etc complete. ( Plinth Protection Area ,Hole area , damaged floor etc) ( qnty as per actual).	Cum	2.45	5762.2	14117.319
8	Removing the debris with mechanical , means within 5 KM from the work site with cost , carriage , royalty labour etc complete	cum	5	151.17	755.85
9	Writing TEXT (REGIONAL BLOOD BANK, IRCS-OSB, BHUBANESWAR )with RED CROSS logo enamel paint to the wall including cost of all the materials labour , T&P etc complete in all the respect. As per the actual cost.	Each	20	350	7,000.00

Total Amount **1,42,578.87**  
 ST (CGST & 12% **17,109.46**  
**1,59,688.33**  
 Say **1,60,000/-**