

### Bill of Quantity

**Name of the Work : Repair and Renovation of existing parking area ( Two wheeler Vehicle ) at IRCS-OSB campus , Bhubaneswar for the FY - 2022-2023**

SI N	Items description	Unit	Quantity	Rate	Amount
1	Re-Fitting & Re-Fixing of GCI sheet in roof drilling hole in wind tiles including fixing of ridges, wind ties etc. complete including cost of all materials , Labour, Scaffolding , sundries , T&P, Cleaning etc completed in all the respect.( qnty as per actual)	sqm	71.6159	168.91	12096.63
	Garage for two wheeler Vehicle Parking adjacent to OSB main building	sqm	71.6159		
2	12 mm thick inside plaster Cement Plaster(1:6) for brick work including cost of all materials , Labour, Scaffolding , Sundries , T&P etc as required for the work and completed in all the respect.( qnty as per actual).	sqm	1.125	139.22	156.62
	Vehicle for two wheeler Parking area	Sqm	1.125		
3	Cement Concrete of proof (1:2:4) using 12 mm size BHG mental including all material , labour cost etc complete. ( Hole area , damaged floor etc ) ( qnty as per actual).		0.252	5815	1465.38
	Grouting	cum	0.252		
4	Priming one coat Wall cement primer of approved shade of new work to give an even shade including all cost material , conveyance , taxes & scaffolding etc complete in all respect.	sqm	1.125	61.76	69.48
	Vehicle for two wheeler Parking area	Sqm	1.125		

NB: The Quantity may be increase or decreases if required , depending on the Building constructions	al Amount		<b>13,788.11</b>
	ST (CGST &	12%	1,654.57
			15,443
	Say		<b>16,000</b>