

BOQ									
Name of the Work : Construction of IRCS-OSB Lawn fencing with Barbed wire and other related work in the premises of IRCS-OSB , Bhubaneswar FY - 2023-24									
Sl No	Items description	Unit	No	Length	Breath	Height	Quantity	Rate	Amount
1	Earth work in hard soil or gravelly soil within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the FIC	Cum					2.70	156.99	424.05
2	Filling foundation and plinth with good coarse sand including watering & ramming as per the specification .	Cum					0.60	508.82	305.42
3	Cement concrete (1:2:4) with 12 mm size hard granite chips (per Cum)	cum					2.701	6552.51	17699.16
4	Providing fitting & fixing Barbed Wire including cost of all material Labour etc complete in all the respect						910	12.26	11,157.81
5	Supplying Fitting & Fixing M S angle / Channel of MS angle 65x65x6mm for posting as a barbed wire pillar including cost of welding , fixing, labour , T&P etc completed in all respect. @ 5.91Kg/rmt	rmt					521.262	49.56	25,834.37
6	Supplying, fitting and fixing of M.S.grill for Gate>window,ventilator ... etc. complete @25kg/sqm including cost of all the materials, Labour & T&P etc completed in all the respect	Kg					31.50	68.8826	2169.80
7	Painting two coats with good enamel paint over a coat of primer / red oxide on iron works including cost, conveyance & taxes of all materials, T&P, labour charges etc complete.	sqm					23.56	154.49	3640.09
8	Cleaning the site and removing the debries to the out side including cost of all labour & materials etc	each	2				2	352	704.00
							Total Amount		<b>61,934.70</b>

Add GST 18% 11,148.25

**73,082.95**

Say 73,100/-

NB: The Quantity may be increase or decreases if required , depending on the Building constructions and the payment should be made as per the actual qnty.

Sd/-  
Honorary Secretary, IRCS-OSB